

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **30/11/2023 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

Name of work:- Providing & fixing ceiling Lights in common area & labs of AMRC top floor at South campus of IIT Mandi.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Electrical works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **15 days** from issue of work order.
3. All damages done during execution of the work is to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be net and nothing extra is to be paid.
5. Contractor shall abide by labour rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge

Sd/-
Assistant Engineer Elect.

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-
Assistant Engineer Elect.

Schedule of Quantity

Providing & fixing ceiling Lights in common area & labs of AMRC top floor at South campus of IIT Mandi

Sr. no.	Description of item	Qty	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Wiring for light point/ fan point/ exhaust fan point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FR PVC insulated copper conductor single core cable etc as required (Group B) as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	18.00	No.			
2	Wiring for circuit/ submain wiring alongwith earth wire with the 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	60.00	Meter			
3	Supplying, Installation, testing and commissioning of pre-wired, Square Recess Down Lighter(595x595 mm) of Wattage 36 W (6500K) directly on ceiling/ wall, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts.	18.00	Each			
Total						

- Note :-
1. Quoted rate should be inclusive of all applicable taxes including GST (nothing extra shall be payable).
 2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Assistant Engineer Elect.