



No. IITMandi(CW)/SE-1562/2023-24/1129-30

Dated:07-02-2024

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **15/02/2024 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand South campus in the presence of intending contractors or their authorized representatives.

Name of work: Providing and fixing ACP sheet in Engineering Complex, Roller Blinds in Academic block A1 and Re-painting of Academic Block at South Campus of IIT Mandi.

----- As Per Schedule Attached -----

Terms & Conditions:-

1. The work will be carried out as per CPWD General Specifications for **Civil Works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **30 days** from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Agency shall abide by labor rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. In case of non-completion of work after the issue of work order, contractor will be debarred for bidding at IIT Mandi for the next one Year.
11. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-
Superintending Engineer

Copy to:-

1. Notice Board.
2. Institute Website

Sd/-
Superintending Engineer

Schedule of Quantity

Name of the work : Providing and fixing ACP sheet in Engineering Complex, Roller Blinds in Academic block A1 and Re-painting of Academic Block at South Campus of IIT Mandi.

Sr. No.	Description of Item	Qty.	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
1	Applying priming coat : a) With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/steel works.	705.00	Sqm			
2	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	370.00	Sqm			
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : a) One or more coats on old work.	705.00	Sqm			
4	Providing and fixing double scaffolding system (cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40mm dia M.S. tube, placed 1.5 metre centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube challis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and/ or pointing and/ or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc, wherever required, if feasible, for inspection of work at required locations with essential safety features for the workmen etc., complete as per directions and approval of Engineer-in-charge. Note :- (1) The elevational area of the scaffolding shall be measured for payment purpose. (2) The payment will be made once only for execution of all items for such works.	76.00	Sqm			
5	Providing and Fixing of Vertical Blinds complete with all components, including drilling holes in wood work/RCC and installation at site. Vertical blinds will have following specifications-Best quality fabric, Dust proof & easy to clean, Durable, Fade Resistance, smooth in movement. Channel used in vertical blinds are of high quality, rust and dust proof with 1.25mm thickness approx width 1.75mm approx, anodised for long life. The Channel is designed with support beam to keep it straight and shall have a pocket for holding fabric in position. The channel is closed from sides with end caps to give a neat look. The tie chain is made of unbreakable ABS plastic. The channel is made as such to facilitate smooth and effortless functioning from right to left and vice versa. All work as per entire satisfaction and direction of Engineer -in-charge including carriage of material in all lead and lift.	18.00	Sqm			

Sr. No.	Description of Item	Qty.	Unit	Rate(In Rs)		Amount (In Rs)
				(In Figure)	(In Word)	
6	Providing and Fixing of Horizontal Blinds complete with all components, including drilling holes in wood work/RCC and installation at site. Horizontal blinds will have following specifications-Made from sturdy and long lasting aluminium, Durable, Affordable, functional and elegant, slimline slots ,smooth in movement. The vanes offer flexibility of light control and privacy .The vanes can be tilted to let in more or less light .Slot width i.e. web strips 25mm approx. The channel used is of heavy and good quality material with 25mm width approx. All work as per entire satisfaction and direction of Engineer -in-charge including carriage of material in all lead and lift.	12.00	Sqm			
7	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : a) For fixed portion i) Powder coated aluminium (minimum thickness of powder coating 50 micron)	41.00	Kg			
8	Providing and fixing 4 mm thick ACP Sheet, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineerin-charge. a) 4 mm thick ACP Sheet	19.00	Sqm			
Total						

Note :- 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).
2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer