



सं०: आई० आई० टी० मण्डी/सी डब्ल्यू/ एस ई-1685/2024-25/2063-64

दिनांक 14/11/2024

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned from registered contractors so as to reach in this office on or before **21/11/2024 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Superintending Engineer, IIT Mandi at Kamand campus in the presence of intending contractors or their authorized representatives.

Name of work: Dismantling of overhead and underground conductor/cable line at North campus of IIT Mandi.

----- As Per Schedule Attached -----

Terms & Conditions: -

1. The work will be carried out as per CPWD General Specifications for **Electrical Works** amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within **20 days** from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Agency shall abide by labor rules and regulations.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay of work will be @ 0.05% per day.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.
11. In case of non-completion of work after the issue of work order, dealers/firms will be debarred for bidding at IIT Mandi for the next one year.

Sd/-

अधीक्षण अभियंता

Superintending Engineer

Copy to:-

1. Notice Board, IIT Mandi.
2. Institute Website, IIT Mandi.

Sd/-

अधीक्षण अभियंता

Superintending Engineer

Schedule of Quantity

Name of work :Dismantling of overhead and underground conductor/cable line at North campus of IIT Mandi.

| Sr. No. | Description of Item | Qty. | Unit | Rate(In Rs) | | Amount (In Rs) |
|--------------|---|--------|-------|-------------|-----------|----------------|
| | | | | (In Figure) | (In Word) | |
| 1 | Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 11 KV grade of Above 120 sq. mm and upto 400 sq. mm direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. | 200.00 | Meter | | | |
| 2 | Dismantling of over head lines comprising of copper/ aluminium over head conductor, G.I. wire, cross arms, insulators etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts. | 200.00 | kg | | | |
| 3 | Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts. | 9.00 | each | | | |
| 4 | Earth work in excavation by mechanical means (hydraulic excavator)/manual means over areas exceeding (30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead up to 50 m and lift up to 1.5 m as directed by Engineer-in-charge. | 80.00 | cum | | | |
| 5 | Dismantling, roll back and separation of messenger wire of 11 KV HT cable 3.5 C x 300 sq mm size aluminium armoured cable laying on ground and partially underground with full care as required as per entire satisfaction and direction of Engineer-in-charge including carriage of material in all leads and lifts. | 900.00 | Meter | | | |
| 6 | Making straight through cable jointing with heat shrinkable jointing kit for 300 sq. mm of 3 core, XLPE aluminium conductor cable of 11 KV grade as required | 3.00 | Each | | | |
| Total | | | | | | |

Note :- 1. Quoted rate should be inclusive of all applicable taxes including GST(nothing extra shall be payable).

2. All Statutory deduction will be made as per prevailing rates.

Sd/-
Superintending Engineer